



New Enterprise Stone & Lime Co., Inc.

Project Spotlight

MasterFiber® MAC 360FF

Macrosynthetic Fiber

Location

New Enterprise, PA

Contractor

Valley View Builders, LLC

Concrete Producer

New Enterprise Stone & Lime Co., Inc.

Concrete Volume

150 cubic yards

Fiber Dosage

3 lbs./cubic yd

Application

Slab on Ground Radiant Heat

Slab was specified 5.5" thick, 4000 psi with rebar #4 @ 24" o.c.e.w. Contractor unable to get the rebar into the top third of the slab due to the placement of heating tubes. Maco fiber allowed maximum crack control at a lower cost. Heating tubes were attached directly to the insulation boards.

Key State Ag Transport LLC



Altoona Sales Area - Adrian "Ace" Snyder - 814.330.2425

Harrisburg & Chambersburg Sales Area - Scott Eichelberger - 717.729.1816

Lancaster Sales Area - Darryl Keiser - 717.286.5894

Allentown Sales Area - Clint Renninger - 484.256.8343